ame of Work :- Development Of Permanent Campus Of Nu Rajgir.								
bject :- Schedule-B								
Sr.no	DSR'14	Total Quantity	Description	Unit	Total Rate of with Cost Index & Local Tax	Total Amount of with Cost Index & Local Tax	DSR/MARKET ESTIMATED RATE	DSR/MARKET ESTIMATED AMOUNT
			General Notes : All the works are to be carried out as per latest specifications of CPWD/MES/Indian Railways/State PWD, and relevant IS Codes unless otherwise specified in BOQ. Measurements of all the items shall be taken as per detailed specifications of the various items mentioned in CPWD specifications. In the absence of such specifications mode of Measurements as per IS 1200 with its latest revisions will be followed. Unless otherwise specified, the rates of various items will be for all heights, leads and lifts. It is deemed that tenderer has understood the intent of the item of work to be completed and cost(s) of item quoted, is worked out to include the cost of all labour & materials and to complete the item of work irrespective of completeness of the description.					
			Note: A) In case any specific method of measurement for any item is not mentioned, IS 1200 shall be followed for the purpose of measurement and certification. B) This BOQ shall be read in conjunction with Technical Specification.					
			General Notes: All levels mentioned in tender/GFC drawing are with respect to existing ground level at site or, for trenches and pits, the bottom of mass excavation, whichever deeper. At the time of handing over the site to the Contractor, if in case, any variation, discrepancy between Good For Construction(GFC)/tender drawings and existing site conditions is noticed, the same should be brought to the notice of Engineer-in Charge/ Architects/Consultants in writing.					
			Levels are to be taken before and after excavation and as directed by Engineer-in-charge for calculating the depth of excavation.					
			Rate shall include marking the areas to be excavated, setting up the reference datum bench mark, establishing interim and final excavation levels with appropriate survey instruments, carrying out excavation in the specified type of soil, inclusive of de-watering to keep the area clear from water ponding at all times to the required depth and profile . Rate shall include for breaking and removing old foundations with or without reinforcement, underground tanks, floor concrete, sewers, pipelines etc. and carting away the debris. Rate shall be inclusive of shoring, strutting, removal of slurry, dewatering, including stacking of good excavated earth anywhere within site premises and backfilling in layers of 300mm to achieve 95 % MDD as approved by Engineer in charge, include all other incidental charges. (Note: Working space and extra space for side slope soil stabilization will not be measured and paid for). Payments will be made only on the volume of earth excavated as per GFC drawings.					
			Contractor shall use the latest mechanical means of excavation suitable to achieve the required excavation level within the agreed time period. All such equipment mobilized on the site shall be in perfectly working condition, well maintained, ensuring no down time during the entire agreed working period. A list of all such equipment, manpower, machinery and the proposed infrastructure that the contractor is going to mobilize for the work shall be submitted to the Engineer in charge before start of work for his approval.					
			The final approved founding strata shall be left absolutely clean by removing loose, slushy soil, murrum and weathered rock with necessary tools & tackles, cleaning the surface by wire brush and carting away debris, dewatering to keep site dry at all times etc. all complete to the approval of Engineer in charge.					
			Contractor's rates shall include fees for all statutory sanction and royalties for any kind of disposal.					
			Quoted rate shall include for cost of materials, labour, loading and unloading charges, hire of machinery, tools & plants, shoring, strutting, dewatering, removal of slurry, fuel charges, transportation, scaffolding and all other incidental charges etc., with all leads and lifts as specified in respective items of work, complete and as directed by the Engineer-in-charge at all levels.					
			If the Excavation for foundation is done to a depth greater than that shown in the drawings or as required by the Engineer -In- Charge, the excess depth shall be made good by the contractor at his own cost with the concrete of the mix used for levelling / bed concrete for foundations. No Payment shall be made to contractor for the cost of Additional Concrete required to fill up the extra depth of excavation in such cases.					
	1		**Pile Work**					
1.001	20.2.3	26104	Boring, providing and installing bored cast-in-situ reinforced cement concrete piles of grade M-25 of specified diameter and length below the pile cap, to carry a safe working load not less than specified, excluding the cost of steel reinforcement but including the cost of boring, with bentonite solution and temporary casing of appropriate length for setting out and removal of same and the length of the pile to be embedded in the pile cap etc. by precussion drilling using direct mud circulation (DMC) or Bailer and chisel technique by tripod and mechanical winch machine all complete, including removal of excavated earth with all lifts and leads (Length of pile for payment shall be measured up to bottom of pile cap). (a) : 450 mm dia piles	Metre	2,147.82	5,60,66,612	1,665.35	4,34,72,296
1.002	20.2.4	199	(b) :500 mm dia piles	Metre	2,519.90	5,01,208	1,953.85	3,88,621
1.003	20.2.5	51259	(c) : 600 mm dia piles	Metre	3,444.81	17,65,77,656	2,671.00	13,69,12,789
1.004	20.2A.1	7293	Boring, providing and installation bored cast-in-situ reinforced cement concrete piles of grade M-25 of specified diameter and length below pile cap, to carry a safe working load not less than specified, excluding the cost of steel reinforcement but including the cost of boring with bentonite solution and temporary casing of appropriate length for setting out and removal of same and the length of the pile to be embedded in the pile cap etc. by **Crawler mounted, telescopic boom hydraulic pilling Rig all complete**, including removal of excavated earth with all its lifts and leads (length of pile for payment shall be measured up to bottom of pile cap). 600 mm dia piles	Metre	4,680.68	3,41,36,173	3,629.25	2,64,68,120

ıme of Work :- Development Of Permanent Campus Of Nu Rajgir.								
bject :- Schedule-B								
Sr.no	DSR'14	Total Quantity	Description	Unit	Total Rate of with Cost Index & Local Tax	Total Amount of with Cost Index & Local Tax	DSR/MARKET ESTIMATED RATE	DSR/MARKET ESTIMATED AMOUNT
1.005	20.6.1.1	80	Vertical load testing of piles in accordance with IS 2911 (Part IV) including installation of loading platform by Kentledge method and preparation of pile head or construction of test cap and dismantling of test cap after test etc. complete as per specification & the direction of Engineer in-charge. Note: 1. Initial and Routine Load Test shall not be carried out by Dynamic method of testing. Note: 2. Testing agency shall submit the design of loading platform for the approval of Engineer-in-charge. (a) : Initial test (Test Load 2.5 times the safe capacity)	Per test	49,733.50	39,78,680	38,561.80	30,84,944
1.006	20.6.1.2	33	(b) :Routine test (Test Load 1.5 times the safe capacity)	Per test	22,469.96	7,41,509	17,422.50	5,74,943
1.007	20.6.2.1	6	Single pile above 50 tonne and up to 100 tonne capacity (a) : Initial test (Test Load 2.5 times the safe capacity)	Per test	60,369.28	3,62,216	46,808.45	2,80,851
1.008	20.6.2.2	1	(b) :Routine test (Test Load 1.5 times the safe capacity)	Per test	34,453.93	34,454	26,714.50	26,715
1.009	20.8.1	17	Lateral load testing of single pile in accordance with IS Code of practice IS : 2911 (Part IV) for determining safe allowable lateral load on pile : (a) :Up to 50 tonne capacity pile	Per test	22,469.96	3,81,989	17,422.50	2,96,183
1.010	20.8.2	1	(b) : Above 50 tonne and up to 100 tonne capacity pile	Per test	35,352.73	35,353	27,411.40	27,411
1.011	20.9	17	Integrity testing of Pile using Low Strain/ Sonic Integrity Test/ Sonic Echo Test method in accordance with IS 14893 including surface preparation of pile top by removing soil, mud, dust & chipping lean concrete lumps etc. and use of computerised equipment and high skill trained personal for conducting the test & submission of results, all complete as per direction of Engineer-in-charge.	Per test	961.48	16,345	745.50	12,674
			Subtotal of Pile Work			**27,28,32,194**		**21,15,45,546**
			Subtotal of NON DSR Work			**0**		**0**
	2	**0**	**Earth work**					
2.001	2.1.1	3616	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth up to 50 m and lift up to 1.5 m, disposed soil to be levelled and neatly dressed : All kinds of soil	100 Sqm	6,505.29	2,35,23,137	5,044.00	1,82,39,104
2.002	2.6.1	217257	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 Sqm on plan) including disposal of excavated earth lead up to 50m and lift up to 1.5m, disposed soil to be levelled and neatly dressed . All kinds of soil	Cum	200.68	4,35,98,817	155.60	3,38,05,159
2.003	2.8.1	8935	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5m, including getting out the excavated soil and disposal surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	Cum	203.13	18,14,959	157.50	14,07,263
2.004	2.3.1	83668	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with 1⁄2 tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead up to 50 m and lift up to 1.5 m : All kinds of soil.	Cum	311.72	2,60,81,212	241.70	2,02,22,556
2.005	2.4	5000	Deduct for not rolling with power roller of minimum 8 tonnes for banking excavated earth in layers not exceeding 20 cm in depth.	Cum	-3.87	- 19,346	-3.00	- 15,000
2.006	MR 2.001	3110	Supplying and Filling the approved good quality earth brought from outside the premises in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with 1⁄2 tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up including all lead and lift.	Cum	874.50	27,19,697	787.84	24,50,177
2.007	2.25	42039	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, compacting each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	Cum	144.96	60,94,112	112.40	47,25,184
2.008	2.26.1	91060	Extra for every additional lift of 1.5 m or part thereof in excavation (DSR Item Nos. 2.1.1, 2.6.1, 2.8.1, 2.3.1) / banking excavated or stacked materials. All kinds of soil.	Cum	59.65	54,31,642	46.25	42,11,525
2.009	2.27	9792	Supplying and filling in plinth with Clean Coarse sand under floors, including watering, ramming, compacting and dressing complete.	Cum	1,173.96	1,14,95,393	910.25	89,13,168
2.010	2.36	1000	Deduct for disposed soil not levelled and neatly dressed.	Cum	-43.79	- 43,786	-33.95	- 33,950
2.011	1.1.2	112730	Carriage of Earth with mechanical Transport (a) up to 1 km Including Loading, Unloading and stacking	Cum	128.25	1,44,57,472	99.44	1,12,09,871
2.012	MR 2.002	500	Carriage of Lime, Murrum, Building rubbish By Mechanical Transport- Disposal up to 5 Km. lead outside campus premises	Cum	278.58	1,39,291	250.98	1,25,488
2.013	2.31	239	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	100 Sqm	827.99	1,97,890	642.00	1,53,438
2.014	2.33.1	15	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material. (a) : Beyond 30 cm girth up to and including 60 cm girth	Nos	253.69	3,805	196.70	2,951
2.015	2.33.2	50	(b) : Beyond 60 cm girth up to and including 120 cm girth	Nos	1,123.47	56,173	871.10	43,555
2.016	2.33.3	23	(c) : Beyond 120 cm girth up to and including 240 cm girth	Nos	5,196.30	1,19,515	4,029.05	92,668
2.017	2.33.4	1	(d) : Above 240 cm girth	Nos	10,421.43	10,421	8,080.45	8,080
2.018	MR 2.003	21988	Providing and Laying Separation Membrane of impermeable plastic sheeting 125 micron thick.	Sqm	26.75	5,88,214	24.10	5,29,923
2.019	MR 2.004	63	Providing & Laying HDPE made empty cement bags and stitching these in periphery so as to make a flexible barricade up to an height of 4 Metre above ground level and erecting with 50 to 60 mm diameter bamboos in frame work of 2400 mm X 1330 mm size including embedding of 600 mm lower part of vertical bamboos in ground as per direction of Engineer in charge	Sqm	226.05	14,128	203.65	12,728

ıme of Work :- Development Of Permanent Campus Of Nu Rajgir.								
ıbject :- Schedule-B								
Sr.no	**DSR'14**	**Total Quantity**	**Description**	**Unit**	**Total Rate of with Cost Index & Local Tax**	**Total Amount of with Cost Index & Local Tax**	**DSR/MARKET ESTIMATED RATE**	**DSR/MARKET ESTIMATED AMOUNT**
2.020	MR 2.005	3	Providing & Laying HDPE made empty cement bags and filling with clod free available excavated earth and stitching the bags manually and placing these filled up bags in form of toe wall to protect the stacked earth as per direction of Engineer-in-charge.(Volume of filled up bags shall be measured for payment purposes)	Cum	1,782.45	5,347	1,605.81	4,817
2.021	MR 2.006	30	Providing & Laying barricading with three rows of enamel painted G.I. Sheets of about 750 mm wide nailed or bolted with wooden poles 80 mm to 100 mm dia spaced 2.4 meter centre to centre. The poles will be embedded in mobile iron pedestal rings suitably framed for giving stable support as per direction of the Engineer-in-charge. All management (including watch and ward) of barricades shall be the full responsibility of the contractor. The barricades shall be removed only after completion of the work or part of the work. After completion of work barricading will be contractor's property	Sqm	248.67	7,460	224.03	6,721
2.022	MR 2.007	9	Removing from one location, a tree of girth not more than 60 Cms. Including the roots by excavating earth around the root, lifting the tree along with earth around the roots by suitable equipment, transporting the tree from old location to the new location, making a pit of required diameter and depth in earth at new location, and replanting the tree in to the pit, back filling the soil around the roots of the tree, including necessary manure, watering the tree for required time till the roots gets hold in the earth at new location complete as directed by Engineer In charge.	Nos	1,004.32	9,039	904.79	8,143
			Subtotal of Earth Work			**13,63,04,594**		**10,61,23,568**
			Subtotal of NON DSR Work			**34,83,177**		**31,37,997**
	3		**Concrete work**					**10,29,85,571**
3.001	4.1.10	100	Providing and laying in position cement concrete of specified grade excluding the cost of cantering and shuttering - All work up to plinth level : (a) : 1:5:10 (1 Cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	Cum	5,163.99	5,16,399	4,004.00	4,00,400
3.002	4.1.5	783	(b) :1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	Cum	6,234.84	48,81,724	4,834.30	37,85,136
3.003	4.1.8	7430	(c) : 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	Cum	5,547.23	4,12,15,933	4,301.15	3,19,57,545
3.004	MR 3.001	211	Providing and laying in position Plum cement concrete of specified grade 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) using plums of 160 mm and more of reasonable size up to a maximum of 20% by volume of Concrete excluding the cost of cantering and shuttering. The Plums should be evenly distributed in concrete and minimum space between two plums should be not less than 200 mm and the plums should not be closure than 150 mm from the surface.	Cum	4,411.80	9,31,993	3,974.59	8,39,633
			Subtotal of Concrete Work			**4,75,46,049**		**3,69,82,714**
			Subtotal of NON DSR Work			**9,31,993**		**8,39,633**
	4		**Reinforced Cement Concrete work**					
4.001	5.9.1	2463	Cantering and shuttering including strutting, propping etc. and removal of form for (a) : Foundations, footings, bases of columns, etc. for mass concrete	Sqm	253.36	6,24,081	196.45	4,83,893
4.002	5.9.2	25387	(b) : Walls (any thickness) including attached pilasters, buttresses, plinth and string courses & kerb etc.	Sqm	465.33	1,18,13,257	360.80	91,59,630
4.003	5.9.3	46854	(c) : Suspended floors, roofs, landings, balconies and access platform	Sqm	518.01	2,42,70,916	401.65	1,88,18,909
4.004	5.9.4	88	(d) : Shelves (Cast in situ)	Sqm	518.01	45,585	401.65	35,345
4.005	5.9.5	57549	(e) : Lintels, beams, plinth beams, girders, bressumers and cantilevers	Sqm	428.38	2,46,52,659	332.15	1,91,14,900
4.006	5.9.6	23477	(f) : Columns, Pillars, Piers, Abutments, Posts and Struts	Sqm	584.69	1,37,26,757	453.35	1,06,43,298
4.007	5.9.7	4683	(g) : Stairs, (excluding landings) except spiral-staircases	Sqm	510.27	23,89,610	395.65	18,52,829
4.008	5.9.9	897	(h) : Arches, domes, vaults up to 6 m span	Sqm	1,375.22	12,33,569	1,066.30	9,56,471
4.009	5.9.14	350	(i) : Extra for shuttering in circular work	Sqm	103.60	36,261	80.33	28,116
4.010	5.9.15	293	(j) : Small lintels not exceeding 1.5 m clear span, moulding as in cornices, window sills, string courses, bands, copings, bed plates, anchor blocks and the like	Sqm	253.36	74,109	196.45	57,462
4.011	5.9.19	130	(k) : Weather shade, Chajjas, corbels etc., including edges	Sqm	634.99	82,548	492.35	64,006
4.012	MR 4.001	1480	(L) : Extra for Shuttering (over DSR items Nos. 5.9.2, 5.9.3, 5.9.4, 5.9.5, & 5.9.6)in sloping slabs, beams, columns and walls for chhatries, gopurams, etc. including the edge beams etc. at all levels.	Sqm	259.01	3,83,329	233.34	3,45,341
4.013	MR 4.002	2214	Extra for staging for additional height in shuttering where ever required with adequate bracing, propping etc., including cost of de-shuttering and decentring at all levels over a height of 3.6 m, for every additional height of 3.6 m or part thereof for Suspended roofs, sloping slabs, slabs in curved shape, landing, beams and balconies etc. (only Plan area of staging to be measured and paid for. Staging for vertical walls, columns pardies etc. will not be paid for in any case.)	Sqm	362.61	8,02,959	326.67	7,23,387
4.014	5.22.6	3908940	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. Thermo-Mechanically Treated bars TMT 500 D	Kg	87.83	34,33,19,006	68.10	26,61,98,814
4.015	5.22A.6	1737547	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars TMT 500 D	Kg	87.83	15,26,07,333	68.10	11,83,26,951
4.016	5.33.1	15709	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of cantering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. (Note :- Cement content considered in this item is @ 330 kg/cum. Excess/ less cement used as per design mix is payable/recoverable separately. All works up to plinth level	Cum	8,120.20	12,75,60,243	6,296.15	9,89,06,220
4.017	5.33.2	15659	(b) : All works above plinth level up to floor V level	Cum	9,046.73	14,16,62,718	7,014.55	10,98,40,838

ıme of Work :- Development Of Permanent Campus Of Nu Rajgir.								
ıbject :- Schedule-B								
Sr.no	**DSR'14**	**Total Quantity**	**Description**	**Unit**	**Total Rate of with Cost Index & Local Tax**	**Total Amount of with Cost Index & Local Tax**	**DSR/MARKET ESTIMATED RATE**	**DSR/MARKET ESTIMATED AMOUNT**
4.018	5.34.1	1583	Extra for providing richer mixes at all floor levels. Note:- Excess/less cement over the specified cement content used is payable /recoverable separately. Providing M-30 grade concrete instead of M-25 grade BMC /RMC. (Note:- Cement content considered in M-30 is @ 340 kg/cum)	Cum	98.66	1,56,183	76.50	1,21,100
4.019	5.35	79	Add for using extra cement in the items of design mix over and above the specified cement content therein.	Quintal	957.93	75,820	742.75	58,789
4.020	MR 4.003	5208	Extra Labour for leaving hollow spaces in Burnt brick Masonry/CSE block masonry for RCC Vertical mullians & horizontal transoms (ties) of required size, providing reinforcement bar for mullians & transoms (ties) as per structural drawing corners bars and concreting the same with M25 concrete grade concrete including removal of mortar, dust, etc. from the hollow spaces before doing the concreting complete as per drawing & instruction of engineer- in- charge. Reinforcement concrete & Burnt brick Masonry/CSE block masonry will be paid separately in their respective items.	Metre	228.89	11,92,080	206.21	10,73,946
4.021	5.42.1	1000	Providing and fixing tapered / parallel threaded couplers conforming to IS code on "Reinforcement Couplers for Mechanical Splices of Bars for Concrete Reinforcement - Specification", to reinforcement bars including threading, enlargement at connection by forging, protecting the prepared reinforcement bars and related operations as required to complete the works per direction of Engineer-in-Charge. (The length of the bars in which coupler is to be provided should not be less than 4 metre, no deduction for labour and binding wire saved for not providing lap length shall be made). (a) : Coupler for 16 mm diameter reinforcement bar	Nos	157.80	1,57,796	122.35	1,22,350
4.022	5.42.2	750	(b) :Coupler for 20 mm diameter reinforcement bar	Nos	214.67	1,61,004	166.45	1,24,838
4.023	5.42.3	500	(c) :Coupler for 25 mm diameter reinforcement bar	Nos	296.89	1,48,446	230.20	1,15,100
4.024	5.43.2	649	Providing and fixing in position Stainless steel Grade 304 plate-1.0 mm thick as per design for expansion joints. (a) : 300 mm wide.	Metre	1,074.33	6,96,701	833.00	5,40,201
4.025	MR 4.004	15	Providing & fixing premoulded compressible filler board of approved make conforming to as per manufacturer specification, including cost of primer in expansion joints as per drawing, specification and sample approved and as directed by engineer in charge.	Cum	81,225.48	12,11,519	73,176.11	10,91,458
4.026	MR 4.005	3891	Providing and laying polysulphide sealant for expansion joints of approved make Including surface preparation, applying primer, backer rod, sealant, curing make as per drawing, manufacturer specification to give water tightness & as directed by engineer in charge.	Sq.Cm x Rmt.	140.42	5,46,391	126.51	4,92,244
4.027	MR 4.006	130	Providing and fixing expansion joint flexible strip with polyurethane sealant of approved make flush mounted expansion /seismic joint system with+/-25mm joint movement design as per the joint manufacturer specification complete as per drawing, specification and sample approved and as directed by engineer in charge.	Sqm	15,418.50	19,99,779	13,890.54	18,01,603
4.028	MR 4.007	126	Making core cutting for fixing pipe 50 mm to 100 mm dia in RCC slab/wall/beam up to 350 mm wide (length of Core cutting) for drainage line fittings as per detailed drawing and as directed by engineer in charge.	Nos	1,556.79	1,96,155	1,402.51	1,76,716
4.029	MR 4.008	186	Making core cutting for fixing pipe 150 mm dia in RCC slab/wall/beam up to 350 mm wide (length of Core cutting) for drainage line fittings as per detailed drawing and as directed by engineer in charge.	Nos	1,895.22	3,52,511	1,707.41	3,17,577
4.030	MR 4.009	66	Making core cutting for fixing pipe 230 mm dia in RCC slab/wall/beam up to 350 mm wide (Length of Core cutting) for drainage line fittings as per detailed drawing and as directed by engineer in charge.	Nos	2,978.20	1,96,561	2,683.07	1,77,082
			Subtotal of Reinforced Cement Concrete Work			**85,23,75,888**		**66,17,69,413**
			Subtotal of NON DSR Work			**68,81,284**		**61,99,355**
	5		**Brick work**					
5.001	6.1.2	13212	Brick work with common burnt clay F.P.S. (non modular) bricks of size 230 mm x 110 mm x 70 mm class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	6,032.29	7,96,98,634	4,677.25	6,17,95,827
5.002	MR 5.001	703	Extra rate over DSR item no. 6.1.2 for Brick work with burnt clay (non modular) bricks of 230 mm x 110 mm x 50 mm size instead of size 230 mm x 110 mm x 70 mm of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	2,019.95	14,20,025	1,819.77	12,79,302
5.003	6.4.2	2282	Brick work with common burnt clay F.P.S. (non modular) bricks of size 230 mm x 110 mm x 70 mm class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	6,998.15	1,59,69,789	5,426.15	1,23,82,474
5.004	MR 5.002	879	Extra rate over DSR item no. 6.4.2 for Brick work with burnt clay (non modular) bricks of 230 mm x 110 mm x 50 mm size instead of size 230 mm x 110 mm x 70 mm and class designation 7.5 in superstructure above plinth level for all levels in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	2,194.64	19,29,089	1,977.15	17,37,918
5.005	6.13.2	5185	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in Cement mortar 1:4 (1 cement :4 coarse sand)	Sqm	858.69	44,52,299	665.80	34,52,173
5.006	6.23	62	Honey-comb brick work 10 / 11.4 cm thick with common burnt clay bricks of class designation 7.5 in super structure above plinth level up to floor V level in cement mortar 1:4 (1 cement : 4 coarse sand).	Sqm	559.48	34,687	433.80	26,896
5.007	6.44	500	Brick edging 7cm wide 11.4 cm deep to plinth protection with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 including grouting with cement mortar 1:4 (1 cement : 4 fine sand).	Metre	49.20	24,601	38.15	19,075
5.008	6.38	250	Providing and laying autoclaved aerated cement blocks masonry with 100 mm thick AAC blocks in super structure above plinth level up to floor V level in cement mortar 1:4 (1 cement : 4 coarse sand). The rate includes providing and placing in position 2 Nos 6 mm dia M.S. bars at every third course of masonry work.	Cum	8,237.31	20,59,327	6,386.95	15,96,738

ıme of Work :- Development Of Permanent Campus Of Nu Rajgir.								
ıbject :- Schedule-B								
Sr.no	**DSR'14**	**Total Quantity**	**Description**	**Unit**	**Total Rate of with Cost Index & Local Tax**	**Total Amount of with Cost Index & Local Tax**	**DSR/MARKET ESTIMATED RATE**	**DSR/MARKET ESTIMATED AMOUNT**
5.009	MR 5.003	14453574	Manufacturing the Compressed Stabilized Earth (CSE) Blocks of size 230 mm x 110 mm x 100 mm, from the selected soil available from excavation at site within premises including providing and installing, operating and maintaining necessary machinery by the contractor at his own cost for the production of CSE blocks. Rates includes required quantity of Selected soil for the production of CSE blocks will be excavated from the site from the Water bodies and transported to the location of CSE blocks manufacturing facility by the contractor. The contractor shall provide necessary Cement, sand and Surkhi etc. at his cost including the supply, transportation to site, royalties etc. The proportion of materials will be as follows (1) Soil/Earth 30 to 40% by weight (2) Sand 30 to 40% by weight (3) Finely ground surkhi which is obtained by gridding well burnt red brick bats available as wastage from red bricks manufacturing kilns, 30 to 40% (4) Cement 8 to 10% by weight but in no case less than 8%. (5) Hydrated Lime 5% The blocks must be cured with moist air or by covering with water soaked gunny bags over the stake of earth blocks for four weeks. The Blocks are allowed to dry for at least 10 days under the shade. The Cured earth blocks are to be staked neatly at the storage yard which will be covered with Ploythene sheets to retain the moisture inside the Earth blocks. Compressive strength of	Nos	10.98	15,86,56,050	9.89	14,29,33,378
5.010	MR 5.004	40529	Brick work with Compressed Stabilized Earth (CSE) Blocks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand) Rates to include transportation of Compressed Earth blocks from storage yard to the site of work. (Supply of CSE block will be paid separately in relevant items)	Cum	3,632.81	14,72,33,974	3,272.80	13,26,43,220
5.011	MR 5.005	5336	Half brick masonry with Compressed Stabilized Earth (CSE) Blocks of class designation 7.5 in superstructure above plinth level up to floor V level in: Cement mortar 1:4 (1 cement :4 coarse sand) Rates to include transportation of Compressed Earth blocks from storage yard to the site of work. (Supply of CSE block will be paid separately in relevant items)	Sqm	424.93	22,67,427	382.82	20,42,727
5.012	6.5	100	Extra for brick work / AAC block masonry / Tile brick masonry in superstructure above floor V level, for each four floors or part thereof by mechanical means.	Cum	372.79	37,279	289.05	28,905
5.013	6.14	75	Extra for half brick masonry in superstructure, above floor V level for every four floors or part thereof by mechanical means.	Sqm	33.02	2,476	25.60	1,920
5.014	MR 5.006	15877	Extra rates over DSR item no. 6.4.2 for providing exposed masonry with common burnt clay bricks of size 230 mm x 110 mm x 70 mm including raking horizontal and vertical joints 10 mm wide 12 mm deep to receive pointing complete. The Exposed surface area only of the Brick work will be measured for payment.	Sqm	81.86	12,99,644	73.75	11,70,851
5.015	MR 5.007	4693	Extra rates over MR item no. 5.002 for providing exposed masonry work for Brick masonry with common burnt clay bricks of size 230 mm x 110 mm x 50 mm instead of size 230 mm x 110 mm x 70 mm , including raking horizontal and vertical joints 10 mm wide 12 mm deep to receive pointing complete in cement mortar 1:4 (1 cement : 4 coarse sand). The Exposed surface area only of the Brick work will be measured for payment.	Sqm	13.46	63,179	12.13	56,918
5.016	MR 5.008	60647	Extra rates over MR item no. 5.004 for providing exposed masonry with Compressed Stabilized Earth (CSE) Blocks including raking horizontal and vertical joints 10 mm wide 12 mm deep to receive pointing complete. The Exposed surface area only of the Brick work will be measured for payment.	Sqm	67.50	40,93,568	60.81	36,87,899
			Subtotal of Brick Work			**41,92,42,048**		**36,48,56,220**
			Subtotal of NON DSR Work			**31,69,62,956**		**28,55,52,213**
	6		**Stone work**					
6.001	7.1.1	11	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	5,053.21	56,849	3,918.10	44,079
6.002	7.8.1	18	Coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and up to floor five level Masonry work (first sort) , in cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	6,788.51	1,18,799	5,263.60	92,113
6.003	7.32.1	100	Stone work, plain in copings, cornices, string courses and plinth courses, up to 75 mm thick in Cement mortar 1:6 (1 cement : 6 coarse sand), including pointing with white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade. - Red Sandstone	Cum	49,330.08	49,33,008	38,249.00	38,24,900
6.004	MR 6.001	781	Providing and fixing wet cladding in (wall lining) any shape at all heights with 18 to 20 mm thick gang saw cut stone with (machine cut edges) of uniform colour and size, backing filled with a grout of average 12 mm thick cement mortar 1:3 (1 cement : 3 coarse sand) mixed with adhesive in proportion as per manufacture's specification, including pointing in white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade at all levels including cutting, making recesses in stone slab, drilling holes, rubbing, polishing, curing, and scaffolding etc. complete in the required pattern as per drawing and as directed by engineer in charge. (a) : Red Sandstone	Sqm	2,647.62	20,67,792	2,385.24	18,62,876
6.005	MR 6.002	10	(b) : Granite stone	Sqm	5,109.39	51,094	4,603.06	46,031
6.006	MR 6.003	4001	Providing and fixing Jali (Grill) in the openings in Brick/RCC wall. Jali shall be made out of Red Mandana stone of size up to 320 mm x 150 mm x 30 mm thick, Sand Blasted on all the surfaces, two rows of 25 mm NB MS pipes (heavy class with Minimum wall thickness 2.6 mm) and 40 mm NB x 48 mm long Ms pipe sleeves. Jali shall be fixed as per drawings and as directed by the Engineer in charge complete. Set of 2 nos. M.S. Pipes of 25 mm NB shall be fixed horizontally, on vertical jamb of the opening, side by side at 100 mm centre to centre, from one end of opening to the other end with suitable holdfasts or anchor fasteners. Such set of two pipes shall be fixed from top line of opening to bottom line of opening, at 330 mm centre to centre vertically. Stone pieces shall be placed perpendicular to these pipes, vertically between two sets of pipes, in such a way that 320 mm x 30 mm face of the stone shall be visible in elevation. Stone should have two nos. round shaped grooves on each face at top and bottom faces for resting the stone between 25 mm NB MS pipes as shown in the drawing. 40 mm NB x 48 mm long MS pipe sleeves shall slip over the 25 mm NB pipes to act as spacers between two stones, which are vertically resting on the pipes. Horizontal clear space between two adjacent stones in the same level shall be 100 mm. Horizontal clear Space between two adjacent stones in two adjacent upper and lower levels shall be kept 50 mm. MS pipes and Spacers shall be painted with Epoxy Paint over a cost of suitable Primer before fixing of stones.	Sqm	6,967.87	2,78,78,449	6,277.36	2,51,15,720
6.007	7.33.1	8	Providing and fixing stone jali 40 mm thick throughout in cement mortar 1:3 (1 cement : 3 coarse sand), including pointing in white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment, matching the stone shade, jali slab without any chamfers etc. at all levels as directed by engineer in charge. **Red sand stone**	Cum	12,281.51	98,252	9,522.70	76,182
			Subtotal of Stone Work			**3,52,04,243**		**3,10,61,899**
			Subtotal of NON DSR Work			**2,99,97,335**		**2,70,24,626**
	7		**Marble & Granite Work**					

ıme of Work :- Development Of Permanent Campus Of Nu Rajgir.

ıbject :- Schedule-B

Sr.no	DSR'14	Total Quantity	Description	Unit	Total Rate of with Cost Index & Local Tax	Total Amount of with Cost Index & Local Tax	DSR/MARKET ESTIMATED RATE	DSR/MARKET ESTIMATED AMOUNT
7.001	8.2.2.2	932	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills , facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels .(a) : Granite of any colour and shade Area of slab over 0.50 Sqm	Sqm	5,039.41	46,96,729	3,907.40	36,41,697
7.002	8.3.2	1817	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by engineer in charge. (a) : Granite work	Metre	297.47	5,40,505	230.65	4,19,091
7.003	8.5	1484	Extra for providing opening of required size & shape for wash basin/ kitchen sink in kitchen platform, vanity counter and similar location in marble/Granite/stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	Nos	498.60	7,39,925	386.60	5,73,714
7.004	MR 7.001	40	Providing and laying Mirror polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer in- Charge. (a) : Granite Stone of approved shade	Sqm	4,411.14	1,76,446	3,974.00	1,58,960
7.005	MR 7.002	60	Providing and fixing 18mm thick gang saw cut, mirror polished, pre moulded and pre polished, machine cut stone for tread and risers of steps, dedo, jambs, lintels, partition, seat, landing, parapet top , shelves, chajja , sill, divider, and similar locations of required size, machine cut edges ,approved shade, colour and texture laid over 20mm thick base cement mortar 1:3(1 cement : 3 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing edges give high gloss finish etc. complete at all levels as per detailed drawing and as directed by engineer in charge. (a) : Granite Stone of approved shade	Sqm	5,115.36	3,06,922	4,608.43	2,76,506
7.006	8 .12	30	Providing and laying flamed finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge : Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	Sqm	4,184.27	1,25,528	3,244.35	97,331
			Subtotal of Marble & Granite Work			**65,86,055**		**51,67,299**
			Subtotal of NON DSR Work			**4,83,367**		**4,35,466**
	8		**Wood & PVC Work**					
8.001	9.1.1	553	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). (a) : Second class teak wood	Cum	1,18,004.38	6,52,56,420	91,496.90	5,05,97,786
8.002	MR 8.001	150	Providing wood work in frames of panelled shutters for doors, window , clerestory windows and other similar frames, and fixed to the Existing wooden frames with approved make Hinges as per detailed drawings and as directed by the Engineer - in - Charge. The various components of Panelled shutter like vertical stiles, Top, Bottom & lock rails and intermediate transoms & mullions, in the shutter shall be measured, only in volume of teakwood used and shall be paid for. The rates shall include all the required materials like, nails, screws, wooden nails, Adhesive Glue etc. and labour for preparation of shutter frame and fixing the same with Door frames complete. Approved quality Hinges, Wooden/ Glass/Ply wood panels including the necessary Teak wood beading , nails & screws etc. for fixing hinges/panels shall be paid under relevant items as the case may be. (a) : Second class teak wood	Cum	1,50,674.75	2,26,01,212	1,35,743.01	2,03,61,452
8.003	9.7.1	1698	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick : (a) : Second class teak wood panels- 25 mm thick	Sqm	2,780.10	47,20,604	2,155.60	36,60,209
8.004	MR 8.002	484	(b) : Marine Ply wood 19 mm thick	Sqm	3,057.32	14,79,743	2,754.34	13,33,102
8.005	9.7.7.2	6960	(c) : Float glass panes 5.0 mm thick glass panes	Sqm	1,814.30	1,26,27,515	1,406.75	97,90,980
8.006	9.7.8	6073	(d) : Fly proof stainless steel grade 304 wire gauge with 0.5 mm dia. wire and 1.4 mm wide aperture with matching wood beading	Sqm	2,066.63	1,25,50,642	1,602.40	97,31,375
8.007	9.21.1+9.23 - (9.15.1.1)	6160	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters, lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters : (a) : 35 mm thick excluding ISI marked Stainless Steel butt hinges with necessary screws	Sqm	2,543.50	1,56,68,502	1,972.15	1,21,48,866
8.008	9.22.1	127	Extra for Providing and fixing flush doors with decorative veneering instead of non decorative ISI marked flush door shutters conforming to IS: 2202 (Part I) (a) : On one side only	Sqm	509.31	64,682	394.90	50,152
8.009	9.127	12190	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt / suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality. (a) :1.0 mm thick on one side only	Sqm	872.36	1,06,34,058	676.40	82,45,316
8.010	MR 8.003	50	Providing and fixing a pair of Stainless Steel Pivots for making the stone jali openable by fixing Pivot by making necessary recesses in stone jali and RCC/stone sill & Lintel and fixing the pivot with necessary S.S. Screws etc. complete as directed by Engineer In Charge.	Sqm	2,065.14	1,03,257	1,860.49	93,025