TENDER DOCUMENT

Name Of Work*:* Construction of Type-II Apartments (G+10, 80 Nos) including Water supply, Sanitary installation, Internal Electrical installations, Fire Fighting, Fire Alarm system, Lifts and development works at IIT Kanpur.

NIT No: -44/Composite/D3/2024-25

Note-1	The intending bidder must read the terms and conditions carefully. He should submit his bid only if he considers himself eligible and he is in possession of all the documents as required
Note-2	The intending bidder must upload all the documents as detailed in **Para 25 on pages- 10 and 11 of** this document.
Note-3	Applicants are advised to keep visiting www.iitk.ac.in/iwd/tenderhall.htm & https://eprocure.gov.in/eprocure/app from time to time (till the deadline for bid submission) for any updates in respect of the tender documents, if any. Failure to do so shall not absolve the applicant of his liabilities to submit the applications complete in all respects including updates thereof, if any. An incomplete application may be liable for rejection.
Note-4	The EMD shall be prepared in favour of **The Director, IIT Kanpur payable at Kanpur** as detailed in the tender document. A part of EMD is acceptable in the form of bank guarantee as per the details in the tender document. This bank guarantee shall also be in favour of The Director, IIT Kanpur.
Note-5	The defect liability period is 36 months from the date of handing over the completed building to the engineer in charge except for the items specifically mentioned in this tender document. Other related details are elaborated in the tender document.
Note-6	Pre-bid meeting shall be held on 11/03/2025 at 11:00 AM as detailed in this document
Note-7	The construction work is to be carried out at IIT Kanpur campus.

5	Diploma Engineer	1	8	Surveyor	Rs.30000/- pm Per person	Rupees Thirty Thousand per month per person
6	Graduate Engineer	1+1	6	Project Planning/billing Engineer	Rs.40000/- pm Per person	Rupees Forty Thousand per month per person
7	Safety Manager (a graduate with one year full time advance safety diploma from Central Labour/Mumbai/ NICMAR /Hyderabad/Mahatama Gandhi Labour Institute Ahmedabad or an equivalent Qualification	1+1	Ten Year in major Construction/ Infrastructure Project.	Safety Manager	Rs.60000/- pm Per person	Rupees Sixty Thousand per month per person

Assistant Engineers retired from Government services who are holding Diploma will be treated at par with Graduate Engineers.

Clause 38

(i)	(a)	Schedule/statement for determining theoretical quantity of cement, bitumen etc on the basis of Schedule of Rates	Delhi Schedule of Rates 2023 with correction slips up to the last date of receipt of tenders
(ii)		Variations permissible on theoretical quantities:	
	(a)	Cement	±(plus/minus) 2% (Two percent)
	(b)	Bitumen for all works	+ (plus) 2.5% (Two point five percent) only and nil on – (minus) side.
	(c)	Steel Reinforcement and structural steel sections for each diameter, section and category	+ (plus) 2.0% (Two percent) only and nil on – (minus) side.
	(d)	Paint	As per co-efficient of standard Delhi Analysis of Rate 2023.
	(e)	Any other item viz fire rated paint etc.	As per manufacturer specification

ANNEXURE - II

Milestone chart

Sl. No.	Description of mile stone	Period for completion from date of start	Withheld amount for non achievement of mile stone.
1	**A- Activity Completion of Civil Work:** (a) RCC of Foundation upto plinth level **B- Activity completion of E&M work:** a) Submission of eligibility documents of associate agencies for E&M works as per eligibility condition. (b) Submission of shop / layout drawings for conduits / equipments of EI, Fire fighting, Lift, CCTV etc. as required for all E&M services. **or** Gross value of work done not less than 5 % of the accepted tendered value.	2 months	0.5 % of the accepted tendered value.
2	**A- Activity completion of Civil Work:** (a) RCC slab upto floor level 3 (b) Brick work upto floor level 1 **B- Activity completion of E&M work:** (a) Slab conduiting upto floor level 3 (b) Wall conduiting upto floor level 1 **or** Gross value of work done not less than 25 % of the accepted tendered value.	06 months	0.5 % of the accepted tendered value.
3	**A- Activity completion of Civil Work:** (c) RCC slab upto floor level 7 (d) Brick work upto floor level 4 (e) Sample flat at first floor i/c all complete **B- Activity completion of E&M work:** (c) Slab conduiting upto floor level 7 (d) Wall conduiting upto floor level 4 (e) Sample flat at first floor with all wiring, switch, Socket, fan, fitting etc installed & complete **or** Gross value of work done not less than 40 % of the accepted tendered value.	09 months	0.5 % of the accepted tendered value.

4	**A- Activity completion of Civil Work:** (a) RCC slab upto floor level 10 (b) Brick work upto floor level 7 (c) Internal work i/c flooring upto floor level 2 (d) Water proofing of toilets, internal plumbing work, upto floor level 2 **B- Activity completion of E&M work:** (a) Slab conduiting upto level 10 (b) Wall conduiting, socket boxes and DBs upto level 7 (c) Making of holes in toilets, labs/rooms, lift lobby, lift shaft, etc. pressurization, fire fighting and exhaust etc. upto level 7 **or** Gross value of work done not less than 55% of the accepted tendered value.	12 months	0.5 % of the accepted tendered value.
5	**A- Activity completion of Civil Work:** (a) RCC , slab upto floor 11 ,Over Head water tank, Machine room Complete (b) Brick work upto floor level 9 (c) Internal work i/c flooring upto floor level 5 (d) Water proofing of toilets, internal plumbing work, upto floor level 5 **B- Activity completion of E&M work:** (a)Slab conduiting upto level 11 (b)Wall conduiting, socket boxes and DBs upto level 9 © Making of holes in toilets, labs/rooms, lift lobby, lift shaft, etc. pressurization, fire fighting and exhaust etc. upto level 9 **or** Gross value of work done not less than 70 % of the accepted tendered value.	15 months	0.5 % of the accepted tendered value.

6	**A- Activity completion of Civil Work:** (a) Brick coba complete (b) Completion of Brick work (c) Toilet work including internal plumbing work, wall tiling work upto level 11 (d) completion of all Flooring work etc upto level 10 **B- Activity completion of E&M work:** Submission of inspection call at OEM premises for all major materials such as panels, lift, UPS, equipments, cables etc. and any other materials as required. (a) Wall conduiting, socket boxes and DBs of all floors (b) Making of holes in toilets, labs/rooms, lift lobby, lift shaft, etc. pressurization, fire fighting and exhaust etc. upto all floors (c) Wiring, laying of raceway work completed. **Or** Gross value of work done not less than 85% of the accepted tendered value.	18 months	0.5 % of the accepted tendered value.
7	**Completion of all works in all respect including testing and commissioning**	20 Months	