Form no-1

SCHEDULE OF PRICES & TOTAL PRICES
Tender Schedule

Name of work:- Construction of Type-3 Staff Quarters at REJN, AELN, DBLN, BAGN, SMPN, PMPN & FLN and providing additional floor over existing service building at FLN DFCCIL station in the jurisdiction of CGM Jaipur.

Schedule-A							
DSR Code	**DESCRIPTION**	**QTY**	**UNIT**	**RATE incl GST as per DSR 2021**	**Rate incl. 18% GST (Multifying factor 1.0633)**	**Rate applicable after Escalation (- 38%)**	**AMOUNT**
2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.						
2.8.1	All kinds of soil	2592.00	Cum	286.85	305.01	189.10	4,90,147.20
2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	2112.00	Cum	253.95	270.03	167.42	3,53,591.04
2.27	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	960.00	Cum	2161.20	2298.00	1424.76	13,67,769.60
4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :						
4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	112.00	Cum	7365.15	7831.36	4855.44	5,43,809.28
4.1.5	1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	368.00	Cum	6833.40	7265.95	4504.89	16,57,799.52

5.2	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :						
5.2.2	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size de rived from natural sources)	120.00	Cum	10185.05	10829.76	6714.45	8,05,734.00
5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.						
5.33.1	All works upto plinth level						
5.33.1.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	400.00	Cum	7997.30	8503.53	5272.19	21,08,876.00
5.33.2	All works above plinth level upto floor V level						
5.33.2.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	1200.00	Cum	10080.15	10718.22	6645.30	79,74,360.00
5.9	Centering and shuttering including strutting, propping etc. and removal of form for						
5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	592.00	Sqm	307.95	327.44	203.01	1,20,181.92
5.9.19	Weather shade, Chajjas, corbels etc., including edges	488.00	Sqm	814.95	866.54	537.25	2,62,178.00

5.9.3	Suspended floors, roofs, landings, balconies and access platform	4209.00	Sqm	766.55	815.07	505.35	21,27,018.15
5.9.5	Lintels, beams, plinth beams, girders, bressumers and cantilevers	5805.00	Sqm	608.35	646.86	401.05	23,28,095.25
5.9.6	Columns, Pillars, Piers, Abutments, Posts and Struts	4392.00	Sqm	804.25	855.16	530.20	23,28,638.40
	Columns						
5.9.7	Stairs, (excluding landings) except spiral-staircases	344.00	Sqm	657.75	699.39	433.62	1,49,165.28
5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.	-	-	-			
5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	44148.05	Kg	89.65	95.32	59.10	26,09,149.76
5.22A	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.						
5.22A.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	102000.00	Kg	89.65	95.32	59.10	60,28,200.00
6.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:						
6.1.1	Cement mortar 1:4 (1 cement : 4 coarse sand)	235	Cum	6882	7317.63	4536.93	10,66,178.55
6.12	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in :						
6.12.2	Cement mortar 1:4 (1 cement : 4 coarse sand)	185	Sqm	1018.05	1082.49	671.15	1,24,162.75
7.1	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with :						
7.1.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	624.00	Cum	6653.45	7074.61	4386.26	27,37,026.24
6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :	-	-	-			
6.4.1	Cement mortar 1:4 (1 cement : 4 coarse sand)	1560.00	Cum	8512.10	9050.92	5611.57	87,54,049.20
13.1	12 mm cement plaster of mix :						
13.1.2	1:6 (1 cement: 6 fine sand)	5615.00	Sqm	282.00	299.85	185.91	10,43,884.65
13.2	15 mm cement plaster on the rough side of single or half brick wall of mix :						

13.2.1	1:4 (1 cement: 4 fine sand)	11944.00	Sqm	339.70	361.20	223.95	26,74,858.80
13.2.2	1:6 (1 cement: 6 fine sand)	1010.00	Sqm	324.30	344.83	213.79	2,15,927.90
13.11	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).	4752.00	Sqm	442.75	470.78	291.88	13,87,013.76
13.16	6 mm cement plaster of mix :						
13.16.1	1:3 (1 cement : 3 fine sand)	3382.00	Sqm	253.05	269.07	166.82	5,64,185.24
13.26	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	7055.00	Sqm	214.30	227.87	141.28	9,96,730.40
13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	18460.00	Sqm	123.85	131.69	81.65	15,07,259.00
13.41	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :						
13.41.1	New work (two or more coats) over and including water thinnable priming coat with cement primer	20941.00	Sqm	162.55	172.84	107.16	22,44,037.56
13.46	Finishing walls with Acrylic Smooth exterior paint of required shade :						
13.46.1	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	3564.00	Sqm	166.85	177.41	110.00	3,92,040.00
13.47	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade:						
13.47.1	New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	1010.00	Sqm	162.35	172.63	107.03	1,08,100.30
11.16	Precast terrazo tiles 22 mm thick with graded marble chips of size upto 12 mm, laid in floors, and landings, jointed with neat cement slurry mixed with pigment to match the shade of the tiles, including rubbing and polishing complete, on 20 mm thick bed of cement mortar 1:4 (1 cement:4 coarse sand) :						
11.16.1	Light shade pigment using white cement	3302.00	Sqm	1309.90	1392.82	863.55	28,51,442.10

11.41	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.						
11.41.2	Size of Tile 600x600 mm	3082.00	Sqm	1416.65	1506.32	933.92	28,78,341.44
8.31	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	734.00	Sqm	1063.45	1130.77	701.08	5,14,592.72
8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.						
8.2.2	Granite stone slab colour black, Cherry/Ruby red						
8.2.2.2	Area of slab over 0.50 sqm	128.00	Sqm	4425.35	4705.47	2917.39	3,73,425.92
8.3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.						
8.3.2	Granite work	480.00	metre	418.85	445.36	276.13	1,32,542.40

9.21	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:	-	-	-			
9.21.1	35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	588.00	Sqm	2015.75	2143.35	1328.88	7,81,381.44
9.23	Extra for providing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured).	560.00	Sqm	401.40	426.81	264.62	1,48,187.20
9.134	Providing and fixing wire gauge shutters using stainless steel grade 304 wire gauge with wire of dia 0.5 mm and average width of aperture 1.4 mm in both directions for doors, windows and clerestory windows with necessary screws :						
9.134.2	30 mm thick shutters						
9.134.2.2	With ISI marked stainless steel butt hinges of required size						
9.134.2.2.1	Second class teak wood	236.00	Sqm	4153.20	4416.10	2737.98	6,46,163.28
9.48	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete.						
9.48.2	Fixed to openings /wooden frames with rawl plugs screws etc.	1450.00	Kg	197.70	210.21	130.33	1,88,978.50
10.14	Providing and fixing pressed steel door frames conforming to IS: 4351, manufactured from commercial mild steel sheet of 1.60 mm thickness, including hinges, jamb, lock jamb, bead and if required angle threshold of mild steel angle of section 50x25 mm, or base ties of 1.60 mm, pressed mild steel welded or rigidly fixed together by mechanical means, including M.S. pressed butt hinges 2.5 mm thick with mortar guards, lock strike-plate and shock absorbers as specified and applying a coat of approved steel primer after pre-treatment of the surface as directed by Engineer-in-charge:	-	-	-			
10.14.1	Profile B						
10.14.1.1	Fixing with adjustable lugs with split end tail to each jamb	976.00	Rmt	444.50	472.64	293.03	2,85,997.28
10.14.2	Profile-C						