Conversion of SP shed to regular staff quarters including construction of shortfall quarters at JNV Azamgarh(UP)

NIT No. TCIL/C/PD(UP)/NVS/2026/08 **Date: 16.05.2026**

Summary of Cost

Name of Bidder : M/s

S. No.	Description	BOQ Cost in INR	Percentage quoted by the tenderer above/ below/ at par the total amount of BOQ			Quoted Amount (INR)	
			Above/ Below/ At par	% age in figure	% age in Words	in figure	in Words
[1]	[2]	[3]	[4]	[5]	[6]	[7]	[8]
a)	DSR Items and NDSR items	3,07,51,000.00	Above/Below/At par				
	Total Overall Estimated Cost	**3,07,51,000.00**					

NOTE:

1. The tenderer shall furnish their rate in terms of % above/ below/ at par against **OVERALL ESTIMATED COST**

2. If the tenderer choose to opt "At par" under column 4, then the value against 'percentage' in figures in column 5 shall be inserted as '0' (i.e. zero). In such case, if the tenderer fills any value of percentage (other than '0') under column 5, then it will not be given any cognizance and "At par" option (i.e. "Zero" percent) chosen by the tenderer shall take precedence and the amount will be taken as "At par" irrespective of the percentage mentioned under column 5.

3.Bidder will quote its rates inclusive of all charges, costs, taxes, levies etc. including GST, as applicable.
The Estimated Cost put to tender has been reckoned from DSR-2023 (Civil) & DSR-2025 (Electrical) for scheduled items and is inclusive of GST as applicable. Accordingly the bidder shall quote its rates inclusive of all charges, costs, taxes, levies etc. including GST, as applicable considering the latest govt. notifications/ guidelines in this regard.

Date

Place

Seal & Signature of Authorised signatory of Bidder

"Conversion of Staff Quarters in SP Sheds to regular staff quarters at JNV Azamgarh (U.P)"					
SUMMARY OF COST					
S.N.	**Description**	**Amount (Lakh) as per Detail Estimate**			**Remarks**
		DSR-2025	**DSR-2023**	**Market Rate**	
1	TYPE-II QUARTERS TRIPLE STOREY, RCC FRAMED STRUCTURE 8 NOS. (G+1) 1 BLOCK AREA = 693.48 SQM	5.30	196.18	4.90	
2	GUEST HOUSE SINGLE STOREY, RCC FRAMED STRUCTURE AREA = 133.49 SQM	1.26	37.87	0.73	
	SUB TOTAL (A)	**6.56**	**234.05**	**5.63**	
	SUB TOTAL (B)	**246.24**			
	Add for Development	61.27			
	SUB TOTAL (C)	**307.51**			

Detail estimate of "Conversion of Staff Quarters in SP Sheds to regular staff quarters at JNV Azamgarh (U.P)"

S.No.	PARTICULARS OF ITEMS	Amount As per Detailed BOQ		
		DSR-25 Items	DSR-2023 Items	NSR Items
1	**TYPE-II QUARTERS**			
	Civil Work		18,775,048.66	97,488.36
	Plumbing Work		842,998.47	50,562.67
	Electrical Work	529,922.67		341,942.85
	Total	**529,922.67**	**19,618,047.13**	**489,993.88**
2	**GUEST HOUSE**			
	Civil Work		3,578,792.44	-
	Plumbing Work		208,640.98	-
	Electrical Work	125,610.03		72,598.08
	Total	**125,610.03**	**3,787,433.42**	**72,598.08**

Detail estimate of "Conversion of Staff Quarters in SP Sheds to regular staff quarters at JNV Azamgarh (UP)"

(G+1)

SUMMARY OF CIVIL WORK STAFF QUARTERS TYPE II

S. No.	Description	Amount (Rs.)	
1	EARTH WORK	184194.10	
2	CONCRETE WORK	68361.25	
3	REINFORCED CEMENT CONCRETE	6492734.88	
4	BRICK WORK	1822099.70	
5	MARBLE WORK	579320.54	
6	WOOD WORK & PVC WORK	877357.65	
7	STEEL WORK	546916.62	
8	FLOORING	1134123.13	
9	ROOFING	195157.05	
10	FINISHING	1318130.75	
11	ALUMINIUM WORK	862890.83	
	Total for (6 Nos quarters)	**14081286.49**	
	Total for (8 Nos quarters)	**18775048.66**	
	Non DSR Amount	73116.27	
	Total (6 Nos)	**73116.27**	
	Total (8 Nos)	**97488.36**	

Detail estimate of "Conversion of Staff Quarters in SP Sheds to regular staff quarters at JNV Azamgarh (UP)"

COST ESTIMATE OF STAFF QUARTERS TYPE II

S. No.	Ref. No	Description	Unit	Quantity	DSR 23 Rate	Amount (Rs.)
1	2	3	4	5.00	6.00	7.00
1	2	**EARTH WORK**				
1.01	2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
a)	2.8.1	All kinds of soil	Cum	487.00	260.30	126766.10
1.02	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	293.00	196.00	57428.00
		Total of sub-head				**184194.10**
2	4	**CONCRETE WORK**				
2.01	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
a)	4.1.10	1:5:10 (1 Cement : 5 coarse sand (zone-III) : 10 graded stone aggregate 40 mm nominal size)	Cum	9.64	6518.60	62826.27
2.02	4.2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing :				
a)	4.2.3	1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	Cum	0.56	9895.20	5534.98
		Total of sub-head				68361.25
3	5	REINFORCED CEMENT CONCRETE				
3.01	5.9	Centering and shuttering including strutting, propping etc. and removal of form for all heights:				
a)	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	98.82	392.15	38753.99
c)	5.9.6	Columns, Pillars, Piers, Abutments, Posts and Struts	Sqm	527.40	961.30	506989.62
d)	5.9.15	Small lintels not exceeding 1.5 m clear span, moulding as in cornices, window sills, string courses, bands, copings, bed plates, anchor blocks and the like	Sqm	4.86	392.15	1907.42
e)	5.9.16	Edges of slabs and breaks in floors and walls				
f)	5.9.16.1	Under 20 cms wide	metre	134.20	208.55	27987.41
g)	5.9.3	Suspended floors, roofs, landings, balconies and access platform.	Sqm	339.20	927.25	314524.08
h)	5.9.5	Lintels, beams, plinth beams, girders, bressumers and cantilevers.	Sqm	468.75	736.40	345184.05
3.02	5.18	Providing precast cement concrete Jali 1:2:4 (1 cement : 2 coarse sand(zone-III) : 4 graded stone aggregate 6mm nominal size), reinforced with 1.6 mm dia mild steel wire, including centering and shuttering, roughening cleaning, fixing and finishing with cement mortar 1:3 (1 cement: 3 fine sand) etc. complete, excluding plastering of the jambs, sills and soffits.				
a)	5.18.1	50 mm thick	Sqm	3.30	1886.90	6226.77
3.03	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth & above plinth level.				
a)	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	kilogram	30433.00	107.85	3282199.05
3.04	5.30	Add for plaster drip course/ groove in plastered surface or moulding to R.C.C. projections.	metre	26.70	78.40	2093.28
3.05	5.33	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge."(Note :- Cement content considered in this item is @ 330 kg/cum."Excess/ less cement used as per design mix is payable/recoverable accordingly)				
(i)	5.33.1	All works upto plinth level	Cum	94.51	9504.75	898305.35
(ii)	5.33.2	All works above plinth level upto floor V level	Cum	108.37	9860.40	1068563.86

S. No.	Ref. No	Description	Unit	Quantity	DSR 23 Rate	Amount (Rs.)
		Total of sub-head				6492734.88
4	6.00	BRICK WORK				
4.01	6.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				
a)	6.1.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	22.58	7132.25	161062.25
4.02	6.47	Providing and laying autoclaved aerated cement blocks masonry with 150mm/230mm/300 mm thick AAC blocks in super structure above plinth level up to floor V level with RCC band at sill level and lintel level with approved block laying polymer modified adhesive mortar all complete as per direction of Engineer-in-Charge. (The payment of RCC band and reinforcement shall be made for seperately).				
a)			Cum	167.14	8333.65	1392863.43
4.03	6.13	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.				
a)	6.13.2	Cement mortar 1:4 (1 cement :4 coarse sand)	Sqm	218.28	1123.80	245298.68
4.04	6.15	Extra for providing and placing in position 2 Nos 6mm dia. M.S. bars at every third course of half brick masonry.	Sqm	218.28	104.80	22875.34
		Total of sub-head				1822099.70
5	8	MARBLE WORK				
5.01	8.1	Marble work gang saw cut (polished and machine cut) of thickness 18 mm for wall lining (veneer work), backing filled with a grout of average 12 mm thick cement mortar 1:3 (1 cement : 3 coarse sand), including pointing with white cement mortar 1:2 (1 white cement : 2 marble dust) with an admixture of pigment to match the marble shade (To be secured to the backing by means of cramps, which shall be paid for separately)				
a)	8.1.1	Raj Nagar Plain white marble/ Udaipur green marble/ Zebra black marble.				
(i)	8.1.1.2	Area of slab over 0.50 sqm	Sqm	80.41	5938.00	477450.83
5.02	8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels				
a)	8.2.2	Granite of any colour and shade				-
(i)	8.2.2.2	Area of slab over 0.50 sqm	Sqm	13.18	5136.30	67675.89
5.03	8.3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.				
a)	8.3.2	Granite work	Metre	21.96	510.95	11220.46
5.04	8.4	Extra for fixing marble /granite stone, over and above corresponding basic item, in facia and drops of width upto 150 mm with epoxy resin based adhesive, including cleaning etc. complete.	Metre	21.96	568.55	12485.36
5.05	8.22	Providing and fixing adjustable stainless steel cramps of approved quality, required shape and size, adjustable with stainless steel nuts, bolts and washer (total weight not less than 260 gms), for dry stone cladding fixed on frame work at suitable location, including making necessary recesses in stone slab, drilling required holes etc complete as per direction of the Engineer-in-charge	Each	24.00	437.00	10488.00
		Total of sub-head				**579320.54**
6	9	WOOD WORK & PVC WORK				
6.01	9.1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately)				
a)	9.1.1	Second class teak wood	Cum	0.15	142949.70	21819.84
6.02	9.2	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters				
a)	9.20.3	25 mm thick (for cupboard) including ISI marked nickel plated bright finished M.S. Piano hinges IS : 3818 marked with necessary screws	Sqm	12.60	2819.25	35522.55

S. No.	Ref. No	Description	Unit	Quantity	DSR 23 Rate	Amount (Rs.)
8.03	11.46	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joint with white cement & matching pigments etc. complete				
	11.46.1	Size of Tile 500x500 mm	Sqm	24.72	1593.90	39400.47
8.04	11.55	Providing and laying flamed finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge :				
	11.55.1	Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	Sqm	45.45	3186.70	144835.52
8.05	11.56	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge				
	11.56.2	Polished Granite stone slab of all colour and texture except Black, Cherry/Ruby Red	Sqm	64.51	3071.05	198110.98
		Total of sub-head				1134123.13
9.00	12	ROOFING				
9.01	12.22	Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1 m x1 m x 400 micron, finished with 12 mm cement plaster 1:3 (1 cement : 3 coarse sand) and a coat of neat cement, rounding the edges and making and finishing the outlet complete	Each	4.00	298.25	1193.00
9.02	12.50	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin- charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and	Sqm	175.00	738.65	129263.75
9.03	12.52	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.				
a)	12.52.1	GI Metal Ceiling Lay in plain Tegular edge Global white color tiles of size 595x595 mm, and 0.5 mm thick with 8 mm drop; made of G I sheet having galvanizing of 100 gms/sqm (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending	Sqm	34.00	1902.95	64700.30
		Total of sub-head				**195157.05**
10.00	**13**	**FINISHING**				
10.01	13.4	12 mm cement plaster of mix				
a)	13.4.2	1:6 (1 cement: 6 coarse sand)	Sqm	534.37	343.65	183637.37
10.02	13.5	15 mm cement plaster on rough side of single or half brick wall of mix:				
a)	13.5.2	1:6 (1 cement: 6 coarse sand)	Sqm	890.18	395.35	351931.53
10.03	13.16	6mm cement plaster of mix				

S. No.	Ref. No	Description	Unit	Quantity	DSR 23 Rate	Amount (Rs.)
a)	13.16.1	1:3 (1 cement : 3 fine sand)	Sqm	547.60	300.45	164525.28
10.03	13.37	White washing with lime to give an even shade :				
a)	13.37.1	New work (three or more coats)	Sqm	390.43	39.05	15246.11
10.04	13.41	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :				
a)	13.41.1	New work (two or more coats) over and including water thinnable priming coat with cement primer	Sqm	890.62	185.65	165343.99
10.05	13.47	Finishing walls with Premium Acrylic Smooth exterior paint withSilicone additives of required shade:				
a)	13.47.1	New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	Sqm	533.93	171.10	91355.13
10.06	13.50	Applying priming coat:				
a)	13.50.2	With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood)	Sqm	158.64	74.65	11842.62
b)	13.50.3	With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	Sqm	51.52	67.40	3472.48
10.07	13.62	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
a)	13.62.1	Two or more coats on new work	Sqm	210.16	226.25	47549.25
10.1	13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	1814.98	156.05	283226.98
		Total of sub-head				1318130.75
11.00	**12**	**ALUMINIUM WORK**				
11.01	21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
a)	21.1.1	For fixed portion				
b)	21.1.1.3	Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron)	Kg	964.08	539.85	520458.59
11.02	21.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)				
a)	21.1.2.3	Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron)	Kg	494.59	643.45	318242.81
11.03	21.8	Filling the gap in between aluminium frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete.				
a)	21.8.1	Upto 5mm depth and 5 mm width	Meter	250.02	96.75	24189.44
		Total of sub-head				**862890.83**
13		**NON SHEDULE ITEMS**				
13.01	MR	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :				
a)		150 mm	Each	72.00	75.00	5400.00
13.02	MR	Providing and fixing aluminium door buffer of approved make, design and colour with necessary screws etc all complete as directed and specified by the Engineer-in-Charge :	Each	30.00	45.00	1350.00
13.03	MR	Providing and laying 1st quality ceramic glazed Anti skid floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) conforming to IS:15622 in all colours, shades, sizes as approved over 20 mm thick bed of Cement Mortar 1: 4 (1 cement : 4 Coarse Sand) including pointing the joints with white cement and matching pigment etc complete in all respects as per specifications/drawings and to the entire satisfaction to the Architect	Sqm	29.10	1100.00	32014.95

S. No.	Ref. No	Description	Unit	Quantity	DSR 23 Rate	Amount (Rs.)
3.02	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				-
a)	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	kilogram	6,017.00	107.85	648,933.45
						-
3.03	5.30	Add for plaster drip course/ groove in plastered surface or moulding to R.C.C. projections.	Metre	7.45	78.40	584.08
3.04	5.33	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge."(Note :- Cement content considered in this item is @ 330 kg/cum."Excess/ less cement used as per design mix is payable/recoverable separately).				
(i)	5.33.1	All works upto plinth level	Cum	22.62	9,504.75	215,022.34
(ii)	5.33.2	All works above plinth level upto floor V level	Cum	31.72	9,860.40	312,781.23
		Total of sub-head				**1,544,174.41**
4.0	**6**	**BRICK WORK**				
4.01	6.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				
a)	6.1.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	11.39	7,132.25	81,247.53
4.02	6.47	Providing and laying autoclaved aerated cement blocks masonry with 150mm/230mm/300 mm thick AAC blocks in super structure above plinth level up to floor V level with RCC band at sill level and lintel level with approved block laying polymer modified adhesive mortar all complete as per direction of Engineer-in-Charge. (The payment of RCC band and reinforcement shall be made for seperately)	Cum	29.12	8,333.65	242,693.72
						-
4.03	6.13	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.				
a)	6.13.2	Cement mortar 1:4 (1 cement :4 coarse sand)	Sqm	83.94	1,123.80	94,335.14
4.04	6.15	Extra for providing and placing in position 2 Nos 6mm dia. M.S. bars at every third course of half brick masonry.	Sqm	83.94	104.80	8,797.23
4.05	6.44	Brick edging 7cm wide 11.4 cm deep to plinth protection with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 including grouting with cement mortar 1:4 (1 cement : 4 fine sand).	Metre	33.00	59.45	1,961.85
		Total of sub-head				**429,035.47**
5.0	**8**	**MARBLE WORK**				
5.01	8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.				
a)	8.2.2	Granite of any colour and shade				
(i)	8.2.2.2	Area of slab over 0.50 sqm	Sqm	1.65	5,136.30	8,474.90
						-
5.02	8.3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge				-
a)	8.3.2	Granite work	Metre	2.75	510.95	1,405.11
						-