CGM/DFCCIL/Kolkata acting for and on behalf of The President of India invites E-Tenders against Tender No **KKK-EN-QTR-DHN-I-PH-I** Closing Date/Time 22/02/2022 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

Contractors are allowed to make payments against this tender towards tender document cost and earnest money only through only payment modes available on IREPS portal like net banking, debit card, credit card etc. Manual payments through Demand draft, Banker cheque, Deposit receipts, FDR etc. are not allowed.

1. NIT HEADER

Name of Work	Construction of Railway staff quarters with electrification in various stations from Sarmatarn to Koderma station of Dhanbad division of East Central Railway under Jurisdiction of General Manager/Co-Ordination/DFCCIL/Kolkata unit		
Bidding type	Normal Tender		
Tender Type	Open	**Bidding System**	Two Packet System
Tender Closing Date Time	22/02/2022 15:00	**Date Time Of Uploading Tender**	01/02/2022 16:45
Pre-Bid Conference Required	No	**Pre-Bid Conference Date Time**	Not Applicable
Advertised Value	174683187.82	**Tendering Section**	JHARKHAND
Bidding Style	Single Rate for Each Schedule	**Bidding Unit**	
Earnest Money (Rs.)	0.00	**Validity of Offer (Days)**	60
Tender Doc. Cost (Rs.)	0.00	**Period of Completion**	9 Months
Contract Type	Works	**Contract Category**	Expenditure
Bidding Start Date	08/02/2022	**Are Joint Venture (JV) firms allowed to bid**	Yes
Ranking Order For Bids	Lowest to Highest	**Expenditure Type**	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule A-Construction of Three storied (Block of six units) Type -II Quarter in DHN and DDU							145019702.60	Above/ Below/Par
011	Please see Item Breakup for details.				78826162.01	12.46	88647901.80	
	Description:- General work							
012	Please see Item Breakup for details.				8381328.66	15.59	9687977.80	
	Description:- Wood Work							
013	Please see Item Breakup for details.				9954143.40	13.31	11279039.89	
	Description:- Pipeline & Sanitary							
014	Please see Item Breakup for details.				1327211.13	12.46	1492581.64	
	Description:- Roadwork							
015	Please see Item Breakup for details.				15609490.78	13.47	17712089.19	
	Description:- Portland Pozzolana Cement.							
016	Please see Item Breakup for details.				15583024.51	3.96	16200112.28	
	Description:- Reinforcement and Structural Steel							

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule B-Construction of Single storied (Block of two units) Type -II Quarter in DHN and DDU							12408742.28	Above/ Below/Par
011	Please see Item Breakup for details.				6856742.12	12.46	7711092.19	
	Description:- General work							
012	Please see Item Breakup for details.				698444.07	15.59	807331.50	
	Description:- Wood Work							
013	Please see Item Breakup for details.				829511.95	13.31	939919.99	
	Description:- Pipeline & Sanitary							
014	Please see Item Breakup for details.				110600.93	12.46	124381.81	
	Description:- Roadwork							
015	Please see Item Breakup for details.				1300790.90	13.47	1476007.43	

	Description:- Portland Pozzolana Cement				
016	Please see Item Breakup for details.	1298585.38	3.96	1350009.36	
	Description:- Reinforcement and Structural Steel				

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule C-Construction of Single storied (Block of one unit) Type -II Quarter in DHN and DDU							1551844.60	Above/ Below/Par
011	Please see Item Breakup for details.				857096.10	12.46	963890.27	
	Description:- General work							
012	Please see Item Breakup for details.				87305.50	15.59	100916.43	
	Description:- Wood Work							
013	Please see Item Breakup for details.				104346.00	13.31	118234.45	
	Description:- Pipeline & Sanitary							
014	Please see Item Breakup for details.				13825.11	12.46	15547.72	
	Description:- Roadwork							
015	Please see Item Breakup for details.				162602.06	13.47	184504.56	
	Description:- Portland Pozzolana Cement							
016	Please see Item Breakup for details.				162323.17	3.96	168751.17	
	Description:- Reinforcement and Structural Steel							

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule D-Construction of Single storied (Block of one unit) Type -III Quarter in DHN and DDU							1844449.77	Above/ Below/Par
011	Please see Item Breakup for details.				1004434.05	12.46	1129586.53	
	Description:- General work							
012	Please see Item Breakup for details.				104395.69	15.59	120670.98	
	Description:- Wood Work							
013	Please see Item Breakup for details.				108353.34	13.31	122775.17	
	Description:- Pipeline & Sanitary							
014	Please see Item Breakup for details.				13825.11	12.46	15547.72	
	Description:- Roadwork							
015	Please see Item Breakup for details.				205171.25	13.47	232807.82	
	Description:- Portland Pozzolana Cement							
016	Please see Item Breakup for details.				214564.78	3.96	223061.55	
	Description:- Reinforcement and Structural Steel							

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule E-Construction of Single storied (Block of one unit) Type -IV Quarter in DHN and DDU							2218452.67	Above/ Below/Par
011	Please see Item Breakup for details.				1225522.72	12.46	1378222.85	
	Description:- General Work							
012	Please see Item Breakup for details.				118442.16	15.59	136907.29	
	Description:- Wood Work							
013	Please see Item Breakup for details.				130595.87	13.31	147978.18	
	Description:- Pipeline & Sanitary							
014	Please see Item Breakup for details.				13825.11	12.46	15547.72	
	Description:- Roadwork							
015	Please see Item Breakup for details.				231670.97	13.47	262877.05	
	Description:- Portland Pozzolana Cement							
016	Please see Item Breakup for details.				266371.28	3.96	276919.58	
	Description:- Reinforcement and Structural Steel							

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit

Schedule F-Deep Boring							161200.00	Above/ Below/Par
01	011013	200.00	Hour	806.00	161200.00	AT Par	161200.00	
	Description:- Demarcation of DFC ROW debris with M20 RCC (150mmx150mmx1225mm) pillars and Dismantling of structure and Disposal of debris in Andal-Gomoh of Phase-I section Hiring of JCB Machine (in good working condition) for leveling and dressing ground / dismantling structures including disposal of debris through dumpers etc. with contractor's labour, JCB machine, machine operator, fuel etc. The contractor shall arrange road permit for vehicle for all the States of operation, as per instructions of engineer in-charge and vehicle shall not be more than three years old. Payment shall be made for actual working hours at site.							

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule G-Deep Boring and Hand Pump for Quarters							354313.00	Above/ Below/Par
1	011010	1.00	Each	249312.00	249312.00	AT Par	249312.00	
	Description:- Drilling and sinking of deep tube well of size 250x200 mm dia in all classes of rail including hard rock by water jet crossing, pneumatic rtg machine including supplying and sinking of standerd high density polyethene (UPVS) casing pipe of size 225 mm in loose stata extended minimum 01 (one) meter inside hard rock to prevent collapsing of bore. The bottom bore have should be size 200 mm clear internal dia for a minimum depth of 100 m below ground level. The rate shall include supplying and fixing MS cap top for bore well, labour, machinery, materials consumable leading , loading- unloading lead lift in all respect complete. The rate shall also include developement of bore by compressor and testing of yield form three days continuously with minimum 5000 GPH submerible pump. The pump will be supplied by contractor for testing the yield.							
2	011020	1.00	Set	5001.00	5001.00	AT Par	5001.00	
	Description:- Supplying and fixing 50mm dia water level indicator with upto 3800mm long (as required) and 300mm wide wooden gauge with sliding arrangement.							
3	012010	2.00	Set	50000.00	100000.00	AT Par	100000.00	
	Description:- Hand Pump for Quarters							

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule H-Electrical work in connection with "Construction of new quarters for shifting of utility at phase I							11124482.90	Above/ Below/Par
1	011010	428.00	Numbers	938.28	401583.84	AT Par	401583.84	
	Description:- Supply, Fixing, connection & testing of LED light fitting 1X18W,T-8, 4' long, complete with inbuilt LED driver, Make - Crompton, Havells, Bajaj, Polycab or similar (LED Luminarie of the makes as specified above should be as per RDSO's specification for Energy efficient LED based luminaire unit for indoor lighhts to be used in Indian Railway offices and buildings. (Fixing of fitting to be done with proper clamping arrangement as per the site requirement and connection to be done with1.5 sqmm single core copper conductor FRLS by tapping from sub main line including supply of ceiling rose and wires and PVC flexiable pipe) (The complete system of LED lights (including Driver etc) shall be guaranteed for satisfactorily performance and manufacturing defects for period of 60 months from the date of commissioning or 72 months from the date of suppply, whichever is earlier. (Reference: Railway Board's letter no.2006/Elect(G)/150/5 dated 27.03.15).							
2	011020	858.00	Numbers	46.95	40283.10	AT Par	40283.10	
	Description:- Supply of smart LED lamp 9 watt base B-22 input voltage 240V AC(minus 30 percent and plus 20 percent) frequency 50HZ,power factor greater than 0.95,luminues flux(lm) greater than 100, CCT-6500K,Cri greater than 80,beam angle greater than 240 deg,life span greater than 25000 hrs. Operating temp 0 deg to C to (plus) 60 deg C, surge protection up to 2 KV,luminous maintenance (luminues flux decrease less than and equal to 10 percent) warranty 03 years. Lamp shall be meet all safety requirement as per IS:16102(part-1) and performance requirement as per IS:16102(part-1) (The complete system of LED lights (including Driver etc) shall be guaranteed for satisfactorily performance and manufacturing defects for period of 60 months from the date of commissioning or 72 months from the date of suppply, whichever is earlier.(Reference: Railway Board's letter no.2006/Elect(G)/150/5 dated 27.03.15)							
3	011030	1286.00	Numbers	184.86	237729.96	AT Par	237729.96	
	Description:- "Wiring of light point with PVC insulated, sheathed & stranded single core copper conductor(FRLS) 1.5mm2 (Wire Make-Havells, anchor, Finolex, Polycab, Mescab) with ECC in PVC pipe in concealed with proper excavation and refilling the wall with proper plastering of the wall with supply & fixing of switch, ceiling rose/angular batten holder etc(.make Havells, anchor,Legrand, Slemens, L&T,or C&S) "							
4	011040	539.00	Numbers	250.90	135235.10	AT Par	135235.10	