STATE BANK OF INDIA		
Project Name –Construction of Residential Twin Towers at Block No 41, Gift City, Gandhinagar, Gujarat		
SUMMARY OF PROJECT COST (REVISED)		
Sr. No.	**Particulars**	**Amount In Rs**
A i	**CIVIL WORK**	
A ii	**PLUMBING WORK INTERNAL & EXTERNAL**	
B	**FIRE FIGHTING WORK, FIRE ALARM, PA SYSTEM.**	
C	**ELECTRICAL INTERNAL, EXTERNAL, LIFT , DATA & TELEPHONE WORKS**	
D	**SECURITY SYSTEM WORKS – BMS, CCTV, BOOM BARRIER WORKS**	
E	**GARBAGE CHUTE**	
F	**Puzzle Car Parking 96 No. Car**	
G	**HVAC SYSTEM**	
	GRAND TOTAL :-	
Notes:		
1	Above Amount is exclusive of GST	

PROJECT C	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT
	SECTION – A : EARTH WORK				
1	**Excavation in all kinds of soil, including soft murum, hard murum, Soft rock.**				
	Excavation in all kinds of soil, including soft, hard murum, soft rock, wet or dry, in loose and slushy condition including clearing the site removing shrubs, tree roots, rank vegetation etc., to the required level for foundations, trenches, pits, rafts, plinths, plinth area levelling, etc.; to required depth from existing ground level including carting away / disposing of unwanted excavated material, stacking suitable earth for backfilling and disposing off surplus excavated material off the site as per direction of the SBI/APMC at no extra cost; using mechanical/ electrical means such as poclain, JCB, rock breaker, chisel tools, compressor, dumper, dozers etc., bailing/pumping out water with required capacities with dewatering pump of required numbers to keep the site dry at all times at location as directed by APMC/ SBI , including making temporary stepping / sloping, sectioning, trimming, dressing of sides, levelling or grading including sprinkling of water cleaning, removing and excavating loose pockets and consolidating them by backfilling all as directed by SBI / APMC.				
	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas for all lifts and heights / levels including getting out and disposal of excavated earth to the places approved by GIFT city/ Municipal authorities, as directed by SBI / APMC.				
i	From 0 to 6m Height	Cu m	33,670.00		
ii	From 6 to 18m Height	Cu m	59,370.00		
	(2) Qty. of Excavation is inclusive of side Slope and working space. Amount will be paid to the contractor only for excavation within plot area.				
2	**Excavation in all kinds of Hard rock or old foundation**				
	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in Hard rock or old foundation to required (any) depth/ heights and lifts over areas including carting away and disposing off excavated material off the site as per direction of the SBI/APMC at no extra cost; using mechanical/ electrical means such as poclain, JCB, rock breaker, chisel tools, compressor, dumper, dozers etc., bailing/pumping out water with required capacities with dewatering pump of required numbers to keep the site dry at all times at location as directed by APMC/ SBI , including making temporary stepping / sloping, sectioning, trimming, dressing of sides, levelling or grading including sprinkling of water cleaning, removing all as directed by SBI / APMC.				
	Hard Rock	Cum	400.00		

PROJECT C	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT
11e	Sloping Slabs of ramps, staircase				
	M30 grade	Cu m	165.00		
11f	Beam, plinth Beam, Lintel Beam				
i	M30 grade	Cu m	621.00		
12	**All works above plinth level**				
12a	Shear Wall, columns, OH tank pardi				
i	M40 Grade	Cu m	2,870.00		
ii	M35 grade	Cu m	2,840.00		
iii	M30 grade	Cu m	3,565.00		
12b	Slabs, Roofs, balconies, landings, Access platforms				
i	M30 grade	Cu m	4,487.00		
ii	M35 grade	Cu m	25.00		
12c	Floor Beams at all levels/ Lintel beams/ Patli /Sill levels beams				
i	M30 grade	Cu m	3,982.00		
ii	M35 grade	Cu m	25.00		
12d	In sloping slabs and steps for staircase				
	M30 grade	Cu m	555.00		
12e	Chajja concrete				
	M30 grade	Cu m	165.00		

PROJECT C	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT
40	**Multicell polycarbonate panel**				
	Supply and Installation of translucent roof with DPI Flux standing seam multicell polycarbonate panel system. The system with complete assembly of co extruded UV protected multicell panels incorporated into a complete system. Co-extruded UV protected polycarbonate panel system of min 8 mm thick of 900 mm (min.) width with angular daylighting concept. Panels with all fixing accessories to ensure best performance for wind uplift, vibration, oil canning and visual appearance. Panels shall be manufactured with vertical standing seam at both sides of the panel. Panels shall be fixed on Purlin with snap on connectors with double tooth grip lock locking mechanism and will be secured on MS structure (will be paid Separately) with 3 numbers self-drilling screws & trapezoid SS fasteners holding the base of the standing seam offering best stability as per IS codes. Panel shall be with additional End cap/Aluminium U/F profile/ Glazing Bar for ends as required as per approved drawings. Trained and factory authorized labour with supervision to complete the entire panel installation as per drawing & direction of the APMC/SBI. Colour: As per Approval . (Excluding the MS structural framing Works). Make :- FLUX, Lexan, Sunlite, Sunpal or equivalent as approved . (Duct Covering at terrace etc.)	Sqm	40.00		
41	**Rolling shutters with partly grill**				
	Supplying and fixing rolling shutters with partly grill of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 – part 1 and M.S. top cover of required thickness for rolling shutters with ball bearing, mechanical device chain and crank operation etc. and including ready mixed red oxide zinc chromate primer with 2 coats of synthetic enamel paint of approved brand and manufacture up to satisfaction of APMC/ SBI .Complete as per detailed drawing and site instructions of the APMC/ SBI	Sqm	53.00		
42	**M.S. grills of required pattern in frames of windows**				
	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. With cutting, fabricating, welding, hoisting, erecting, fitting, finishing, cleaning including priming coat with approved steel primer & two or more coats of enamel paint & as per approved design/drawing all complete as directed by the APMC/SBI	MT	49.00		
	TOTAL OF SECTION -I	**Rs**			

PROJECT C	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT
	For joint over end laps, the overlaps surfaces must be clean, wiped and heat welded with at hot air welding gun with 100 mm overlap. After application the system should be allowed to cure for 7 days. In case of exposed condition/ Trafficable joint/higher water pressure joints > 1.5 bar up to 3 bars, protect the joint with a metal plate screwed at one end. The Adhesive area can be painted by any acrylic coating as a protective top coat. Leaking cracks on RCC slab :- Clean the identified crack and remove drilling dust before placing the nozzle. Seal and pack the nozzle with fast setting approve brand of waterproofing Instant Leak Plug compound. Injection of cement slurry admixed with admixture Pidicrete AM (225gms/ bag of cement) or equivalent by using 40PSI grout pump. Plasticizing grout additive Dr. Fixit Pidicrete AM or equivalent of approved brand; the product is to be dispensed in water & added to 50 kg of cement at a water cement ratio of 0.4-0 – 0.45. The mixture thus batched is to be used for injection grouting.				
57d	Waterproof Coating :- Providing & applying of High Solid Content, Cold Liquid- Applied Elastomeric Water Proofing Membrane using Brush/ roller / airless spray to form a minimum system thickness of 1.5mm in three coats with a total consumption is 2.5Kg/m² to achieve 1.5mm DFTor as per manufacturer's specification. 2.5 kg/m² is minimum recommended consumption when applied in three layers to achieve a DFT of 1.5 mm to comply with ASTM C 898 Standard Guide for use of High Solid Content, Cold Liquid- Applied Elastomeric Water Proofing Membrane. Allow the membrane to air cure for 7 days before any activity over it. The PU membrane shall be terminated 300mm above FFL, self-curing for 7 days. The Waterproofing material shall have Solids > 85%, Tensile strength > 2 MPa as per ASTM D 412, Elongation > 400% as per ASTM C 1305, crack bridging up to 3.2mm, Shore A Hardness > 50 as per ASTM D 2240, Adhesion to concrete > 1.5Mpa as per ASTM D 903, Water vapor permeability > 14gm / m2 / day.				
57e	Separation Layer :- Providing & Laying more than 100 GSM Geotextile (non-woven polyester) membrane with a min of 100mm wide overlap loosely laid over PU membrane, etc., complete.				
57f	Horizontal Protection - Mortar screed for protection & Slope:- Providing & laying of average 100 mm thick protective screed of M20 grade by keeping minimum 50mm thickness at drainage point with slope 1:100 containing 12 mm, 100% virgin polypropylene fibres @ 0.9 Kg/Cu.m with a broom finish, well compacted, curing for 7 days etc. complete. The screed shall be raised to the wall in the form of vatta to achieve a smooth corner. The screed shall be divided into panels of 4 mtr X 4 mtr with 6 mm wide x10mm deep construction joint and filling the same with PU sealant, confirms to ASTM C-920-S, NS, 25 & BS EN ISO—11600: 2003 Type F & G as per manufacturer specification, etc, complete.				

PROJECT C	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT
65	**Oil Bound Distemper**				
	Providing & Applying of Oil Bound Distemper to new work with acrylic distemper in 2 or more coats over and including water thinnable priming coat, to give even shade of approved colour, shade & quality to new surfaces in two or more coats / up satisfaction APMC/SBI including putty for filling holes, rubbing of surface to make it even and smooth, scaffolding all complete at basements, ground and all floors, height , leads & lifts cleaning etc. Complete as directed by the APMC/SBI. (inside of Lift Shafts Etc.) Make : Nerolac/ Asian/ Berger or approved equivalent make.	Sqm	6,149.00		
66	**Cement paint**				
	Providing & Applying of Cement paint to new work with 2 or more coats to give even shade of approved colour, shade & quality to new surfaces in two or more coats / up satisfaction APMC/SBI including scaffolding all complete at stilts and podiums and all floors, height , leads , lifts cleaning, rubbing of surface to make it even and smooth etc. Complete as directed by the APMC/SBI. (Diaphragm / Retaining wall from inside etc.) make : Asian paints, Shalimar/ Nerolac / Indigo/Jotun / snowcem Topecem, Nitcocem approved equivalent make	Sq m	3,795.00		
	Note: Rates of painting , gypsum, plastering to include cleaning afterwards, necessary scaffolding/Cradle, debris removing, safety netting, labour etc complete.				
	TOTAL OF SECTION -L	**Rs**			

PROJECT C	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT
1.14	Mirror, 4mm thick of make modiguard/ saint gobain etc or equivalent of dimensions as directed by APMC/SBI, complete with flat polished edges, fitted on site on 12 mm BWP marine ply base, base having BTC lipping border and finished with 1 coat of primer followed by 2 coats of enamel paint on all surfaces of ply and lipping. The mirror shall be either pasted on the ply with silicon adhesive and fitted on wall with two ear hooks as per approval complete to the APMC/SBI satisfaction. (for W.B, size 600X600mm)	Sq.mt.	260.00		
1.15	Orissa pattern 'Indian' WC squatting pan with dual flushing valve including all necessary CP fittings, PVC P trap 110mm dia, flanges, adapters, stop cock, PVC connections etc. complete. Approx. size 60 x 40 x 30 cms. (for service staff toilets).	Nos.	2.00		
	Make: Hindware: 20042, Parry ware: CO-117, Cera: Cadell - S 3020102				
	Dual Flush Valve : Make : Jaquar. Model No. : FLV-1089 or of equivalent make from Kohler or Hindware catalogue.				
1.16	White glazed Flat back Urinal Pan with flush valve operated on sensor, flow spreader, CP flush pipe connection, waste coupling, P trap., including all fittings and connections complete. (Staff toilet and Recreation/Common areas)	Nos.	2.00		
	Make – Parryware: New Magnum- C-583, Hindware: Rhine-96008, Cera: Carys S-4020104				
1.0	**SUB TOTAL -SECTION A**	**Rs.**			
2.0	**SECTION B:- DRAINAGE - INTERNAL & VERTICAL DOWN-TAKES**				
	(SOIL, WASTE, VENT AND RAIN WATER PIPES & FITTINGS)				
2.1	Polypropylene pipes as per EN 1451 tested for Soil and Wastewater pipes including all fittings e.g. (plain or door) bends, junction, offsets, coupler, clean-outs, cowls, jointing with rubber ring joint (push-fit), laid at prescribed slope including cutting chase or holes in walls and floors and making good where required including fabricated pipe supports, GI brackets, clamps, U-clips etc complete. Testing by filling with water for 24 hours. (for internal underslung plumbing)				
	(Inside Toilet Area)				
2.1.1	110 mm dia.	R mt	1,488.00		
2.1.2	75 mm dia.	R mt	1,747.00		
2.1.3	50 mm dia.	R mt	1,637.00		
	(Basement + Ground Floor Ceiling Pipe)				