PLINTH AREA RATES AS ON 01.10.2007

ANNEXURE – 1

S. No.	Description	Office/College/Hospital	Schools	Hostels	Residential
1	2	3	4	5	6
1.0 (A)	**RCC FRAMED STRUCTURE (Specifications as per Annexure –II)**	Rates in Rs. per sq. metre			
1.1(A)	RCC framed structure upto six storeys				
1.1.1(A)	Floor ht.3.35 mtr.	13200	9150		
1.1.2 (A)	Floor ht. 2.90 mtr.			9100	9000
1.0 (B)	**RCC FRAMED STRUCTURE (Normal Buildings) (Specifications as per Annexure –V)**				
1.1 (B)	RCC framed structure upto six storeys				
1.1.1(B)	Floor ht. 3.35 mtr.	10900	8650		
1.1.2 (B)	Floor ht. 2.90 mtr.			8600	8500
1.2	**EXTRAS FOR**				
1.2.1	Every additional storey over six storeys upto nine storeys	310	310	310	310
1.2.2	Every additional storey over nine storeys upto twelve storeys	320	320	320	320
1.2.3	Every 0.3 mt. additional height of floor above normal floor height of 3.35 mt./ 2.90 mts.	150	150	150	150
1.2.4	Every 0.3 mt. higher plinth over normal plinth height of 0.6 mt. (on G.F. area only)	150	150	150	150
1.2.5	Every 0.30 mt. deeper foundations over normal depth of 1.20 metre (on G.F. area only)	150	150	150	150
1.2.6	Making stronger foundations to take load of one additional floor at a later date (on area of additional floor only)	1250	1250	1250	1250
1.2.7	Strip foundations in poor soil having bearing capacity less than 10 tonnes/ sqmt.	286	286	286	286
1.2.8	Resisting Earthquake forces	630	630	630	630
1.2.9	R.C.C. Raft foundations (ground floor only)	3560	3560	3560	3560

1.2.10	Pile foundation up to a depth of 15 mts (on ground floor area only.)	6470	6470	6470	6470
1.2.11	Stronger structural members to take heavy load above 500 Kgs./sqm. upto 1000 Kgs./Sqm.	850	850	850	850
1.2.12	Larger modules over 35 sqm.	990	990	990	990
1.3	**BASEMENT FLOOR**				
1.3.1	Floor ht. 3.35 mtrs with normal water proofing treatment with bituminous felt	10452	-	-	-
1.3.2	**EXTRA FOR BASEMENT WITH**				
1.3.2.1	Mastic Asphalt W.P.T.	1144	-	-	-
1.3.2.2	Every 0.3 mt. addl. Height (above 3.35 mt.)	1274	-	-	-
1.3.2.3	Reduction for every 0.5 m. less height of basement than normal height 3.35 mt.	(-) 728	-	-	-
1.4	**FIRE FIGHTING**				
1.4.1	With wet riser system	300	300	300	300
1.4.2	With sprinkler system	450	450	450	-
1.5	**FIRE ALARM SYSTEM**				
1.5.1	Manual Fire Alarm System	-	-	-	155
1.5.2	Automatic Fire Alarm System	300	300	300	-
1.6	**Operation Theatre (OPD) (Extra provision)**	1235	-	-	-
1.7	**Pressurized mechanical ventilation system in the basements (with supply of Exhaust blowers)**	50	50	50	-